

BRUHATH BANGALORE MAHANAGARA PALIKE
SCHEDULE B

NAME OF WORK: Removal of Debris and Desilting of Drain in ward No 16 Jalahalli in Yeshwanthapura
Sub division

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	3190.00	Removing B.S. Slab of drain and stacking	Sqm	65.72	Rupees Sixty Five And Paise Seventy Two Only
2	2030.00	Earthwork in surface excatation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, Culverts, road drains and trenches of pipe line ad cables) and removing the excavated distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposal earth to be levelled after breaking of clods and neatly dressed as per specifications	Cum	166.42	Rupees One Hundred Sixty Six And Paise Forty Two Only
3	3190.00	Refixing stone slabs on drains and pointng in C.M	Sqm	80.56	Rupees Eighty And Paise Fifty Six Only
4	1733.50	Conveying the excavated earth silt debris and over burden earth etc., to a lead of 10 to 15kms distance by using private vehicle including the cost of loading and unloading charges etc., complete.	cum	112.78	Rupees One Hundred Twelve And Paise Seventy Eight Only



Signature of the contractor

Page 1 of 1


Executive Engineer
RRNagara Division
BBMP